

## CHITALDRUG DIVISION.

Abstract Notification, dated 4th March 1903.

Repairing the Nagasamudra Tank Register No. 114 of Molakalmurn Taluk.  
Attention is invited to tenders called for the above work in the *Mysore Gazette*, dated 12th March 1903.

The 11th March 1903.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 12 noon of 22nd March 1903, for additions and alterations to the Sub-Taluk Cutcherry at Hosdurga. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1903.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for additions and alterations to the Sub-Taluk Cutcherry at Hosdurga," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates tendered should include royalty on stones to be paid to Government.

Additions and alterations to the Sub-Taluk Cutcherry at Hosdurga.

Item of work.	Unit.	Extension.	Lock-up	Barr Sepoys' huts.	Additions & alterations.	Total.
Earthwork	C.yd.	307	98	75		480
Burnt stone in mortar	C.ft.	9304	1263	1858		12425
Do arch work	Do	150				150
Burnt brick in chunam	Do	942	4325	493		5760
Cut stone work	Do	66				66
Burnt stone pillars with cuttings grooved	Each	32				32
Burnt stone slabs 6" thick, dressed	S.ft.	324	380	80	73	857
Do do	Do	169				169
Do dressing (nicely)	Do	70				70
Archwork brick in chunam	C.ft.		15			15
Burnt brick in mud	Do			1862		1862
Concrete filling	Do		1012			1012
Plastering with chunam	Sqr.	36.72	66.91	12.71		116.34
Do with mud	Do			33.58		33.58
Whitewashing	Do	36.72	66.91	46.29	80.00	229.92
Pointing with chunam	Do	66.00		2.22		68.22
Flooring with Mangalore square tiles over 3" concrete and cement pointing over (9" gravel).	Do	1.80			13.95	15.75
Flooring with slabs stones over 3" concrete and cement pointed.	Do	10.80				10.80
Filling with gravel (basement)	C.yds.	41				41
Coping with burnt brick in chunam	R.ft.	6				6
Terrace pucca 9" thick	Sqr.	14.93				14.93
Cornice work as per plan	R.ft.	294				294
Teakwood work wrought and put up	C.ft.	251.91	87.23			339.14
Teakwood planks 2" thick to record room	S.ft.	619				619
Wood oiling	Sqr.	15.74	2.68	8.00	22.46	48.88